





NOTES:

1. CASING SHALL BE INSTALLED BY THE JACKING OR BORING METHOD, AS SPECIFIED.
2. CASING JOINTS SHALL BE WELDED IN ACCORDANCE WITH AWWA STANDARD C-206, EXCEPT THAT HYDROSTATIC TESTING WILL NOT BE REQUIRED.
3. REDWOOD SKIDS SHALL BE PROVIDED AS PER DETAIL ABOVE.
4. SIZE AND THICKNESS OF CASING WALL SHALL BE AS REQUIRED.
5. ENDS OF CASING SHALL BE SEALED TO PREVENT ENTRANCE OF FILL MATERIAL, WITH HEAT SHRINKABLE CASING SEAL.
6. A JOINT SHALL BE INSTALLED AT END OF CASING PIPE (SEE DETAIL).

REVISION	DATE
DATE:	JAN. 2003
DRAWN BY:	DBR
CHECKED BY:	AJA
SCALE:	NONE

CITY OF ESCALON

BORING AND JACKING  
DETAILS

APPROVED BY:

*Don Gilman*  
CITY ENGINEER

IMPROVEMENT STANDARD NO. U2